CHITALDRUG DIVISION.

Notification dated 7th May 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 3 P.M. on 3rd June 1940, for constructing Maternity Home at Hosdurga.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing Maternity Home at Hosdurga." The name of the tenderer should also superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan after depositing under "17 (a) P. W. Deposits" Rs. 300 (Rupees three hundred) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 3rd June 1940 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and the tender notification may be obtained from that officer on payment of four annas.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumsump amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the *nomenclature* of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 20 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Chamundi Brand Cement should to be used.

24. All lumpsum items will be measured and paid at lowest schedule rates.

Abstract of the estimate for constructing a Maternity Home at Hosdurga, Chitaldrug District.

No.	Particulars of work	Quantity.	Per	Rate	Rates tendered in	
					Figures	Words
	Block 1.			Rs. a. p.	Rs.	Rs.
1	Earthwork excavation for foundation and filling in basement	42	C.yd.	0 3 0		
2	Concrete broken stone jelly in lime mortar	359	C.ft.	0 3 0		
3	Size stone in lime mortar	1,154	C.ft.	0 4 6		
4	Burnt brick in mortar superstructure ..	1,739	,,	0 4 0		
5	Cement concrete basement slabs of 1 : 3 : 6	74	,,	0 10 0		
6	Burnt stone slabs 6″ thick exposed faces two line dressed and fixed in mortar.	75	S.ft.	0 5 0		
7	Teakwood doors fully panelled with 1½″ thick shutters including iron fittings complete	105	,,	1 8 0		
8	Teakwood windows with 1¼″ shutters half panelled and half glazed with iron bars, iron fittings, etc., complete	78	,,	2 0 0		
9	T. W. glazed ventilators	12	,,	1 0 0		
10	Teakwood wrought and put up with wood oiling two coats	56	C.ft.	5 0 0		
11	Roofing with first class Mangalore tiles on 2″×1″ T. W. reepers, with nails and double reepers at ends, etc. ..	14·66	Sqr.	25 0 0		
12	Plastering with lime mortar	36·51	,,	3 0 0		

No.	Particulars of work	Quantity	Per	Rate	Rates tendered in	
					Figures	Words
				Rs. a. p.	Rs.	Rs.
13	White-washing two coats	36·51	Sqr.	0 4 6		
14	Flooring with cement concrete (1 : 2½ : 5) 1½″ thick over 3″ bed of lime concrete with ½″ cement plaster finish at top	7·1	,,	18 0 0		
15	Painting doors and windows with Govt. green paint	3·36	,,	4 0 0		
16	Mangalore ridge tiles set in mortar and cement pointed	49	R.ft.	0 8 0		
17	Brick in mortar "Dindu" 9″×9″ including plastering	52	R.ft.	0 4 0		
18	Teakwood plain eave board ⅜″ thick and 9″ deep with two coats of approved paint, etc.	98	,,	0 12 0		
19	Cement pointing to basement ..	2·05	Sqr.	4 0 0		
20	Rolled steel joists ridge and purlin ..	13·1	Cwt.	15 0 0		
21	Constructing sinks in sterilizing and bath rooms		L. S.			
22	Miscellaneous and unforeseen charges ..		,,			
	Block 2.					
1	Earthwork excavation for foundation and filling in basement	45	C.yd.	0 3 0		
2	Concrete broken stone jelly in lime mortar	383	C.ft.	0 3 0		
3	Size stone in lime mortar	1,218	,,	0 4 6		
4	Burnt brick in lime mortar superstructure	1,746	,,	0 4 0		
5	Cement concrete 1 : 3 : 6 basement slab.	79	,,	0 10 0		
6	Burnt stone slabs 6″ thick exposed faces two lines dressed and fixed in mortar	82	S.ft.	0 5 0		
7	Teakwood doors fully panelled with 1½″ thick shutters with iron fittings, etc., complete	124	,,	1 8 0		
8	Teakwood windows half panelled and half glazed with 1¼″ thick shutters with iron bars, iron fittings, etc., complete	90	,,	2 0 0		
9	T. W. glazed ventilators	12	,,	1 0 0		
10	T. W. wrought and put up with wood oiling two coats	66·9	C.ft.	5 0 0		
11	Roofing with first class Mangalore tiles on 2″×1″ T. W. reepers with nails and double reepers at end, etc., complete	14·66	Sqr.	25 0 0		
13	Plastering with lime mortar ..	37·47	,,	3 0 0		
14	White washing two coats	37·47	,,	0 4 6		
15	Flooring with cement concrete, (1 : 2½ : 5) 1½″ thick over 3″ bed of lime concrete, with ½″ cement plaster finish at top	7·64	,,	18 0 0		
16	Painting doors and windows with Govt. factory paint	3·93	,,	4 0 0		
17	Mangalore ridge tiles set in mortar and cement pointed	49	R.ft.	0 8 0		
18	Brick in mortar "Dindu" 9″×9″ including plastering	52	,,	0 4 0		

No.	Particulars of work	Quantity	Per	Rate	Rates tendered in	
					Figures	Words
				Rs. a. p.	Rs.	Rs.
19	Teakwood plain eave board $\frac{3}{4}$″ thick and 9″ deep with two coats of approved paint	98	R.ft.	0 12 0		
20	Cement pointing to basement ..	2·05	Sqr.	4 0 0		
21	Providing sinks in bath and kitchen ..	..	L. S.	..		
22	Miscellaneous and other unforeseen charges	..	,,	..		
1	Constructing compound wall, size stone in mud foundation and basement brick in mortar compound wall with R.C.C. fret work as per design, plastering pillasters and white-washing, etc., complete	30	R.ft.	2 8 0		
2	Supplying and fixing iron gates ..	2	No.	37 8 0		
	Visitors' Kitchen.					
1	Earthwork excavation for foundation..	7	C.yd.	0 3 0		
2	Size stone in clay	276	C.ft.	0 3 0		
3	Burnt stone slabs 6″ thick over basement	92	S.ft.	0 5 0		
4	Superstructure of burnt brick in clay ..	425	C.ft.	0 3 0		
5	Teakwood doors battened with iron works complete	39	S.ft.	1 6 0		
6	Teakwood ventilators with battened shutters, iron bars, etc., complete..	24	,,	1 8 0		
7	Teakwood wrought and put up ..	16	C.ft.	5 0 0		
8	Burnt stone slabs 6″ thick, roughly dressed and fixed in mortar ..	59	S.ft.	0 5 0		
9	Roofing with Mangalore Tiles, complete.	2·80	Sqr.	25 0 0		
10	Plastering with chunam mortar ..	7·93	,,	3 0 0		
11	White washing two coats	7·93	,,	0 4 6		
12	Painting with Government factory green paint, two coats	1·26	Sqr.	4 0 0		
13	Constructing sinks	..	L. S.	..		
14	Cement pointing to basement ..	0·60	Sqr.	4 0 0		
15	Constructing building wall	45	C.ft.	0 4 0		
16	Flooring with cement concrete 1″ thick over 3″ lime concrete and cement plastering on top	1·28	Sqr.	18 0 0		
17	Contingencies	..	L. S.	..		

B. TIRUMALA CHAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated* 19*th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.